

BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 64

NO:BBMP/EE/YNK.D/EPMT-01/2020-21 Dt:02-5-2020

APPROVED TENDER SCHEDULE - 'B'

Item 71

Name of Work :-Improvements to roads and drains main and cross roads of Sharada nagara in ward no - 04.

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri Sathish M	
				Rate	Rate in Words
1	Removing and refixing stone slabs of drains and pointing in CM (1:3) (P. No-27, I. No-5.33)	Sqm	184.32	109.07	One Hundred Nine Paise Seven Only
2	KSRRB 300: Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 m and an average lift upto 0.5 m. excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (P.No-143, I.No-19.1)	Cum	275.33	210.97	Two Hundred Ten Paise NinetySeven Only
3	Providing and Fixing pre cast covering Slab 1000mm thick made out of CC 1:1.5:3 and jelly 20mm Down size with steel reinforcement including form work, curing, including form cost of all materials, labour, hire charges of Machinery, loading, unloading, laid and lift, transportation etc., complete. As per Engineer IN charge. (Data Rate).	Sqm	184.32	2290.26	Two Thousand Two Hundred Ninety Paise TwentySix Only
4	KSRRB M2100-10: Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @ 0.89 cum and fine aggregates @ 0.46 cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centring complete as per specifications. (P. No-222, I. No-27.18)	Cum	4.93	5313.48	Five Thousand Three Hundred Thirteen Paise FortyEight Only

	providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centring, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2000. Including cost of materials, labour, HOM complete as per specifications. (Page No.271. Item No,37.59.2 of PW, P&IWTD S.R 2018-19)	Cum	12.09	6928.80	Six Thousand Nine Hundred TwentyEight Paise Eighty Only
6	KSRRB M2300-14: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour HOM of machinery complete as per specifications. Specification NO. MORTH Specification No.1600 & 2200 TMT Bars Fe 500. (Page No. 239. Item No. 29.29.2 of PW P&IWTD S.R 2018-19)	Tonne	1.09	72512.40	SeventyTwo Thousand Five Hundred Twelve Paise Fourty Only
7	Providing and Fixing RCC pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work, laid and lift charges, curing and concrete finished surfaces on both sides etc., complete. As per Engineer IN charge. (Data Rate).	Sqm	26.28	5309.64	Five Thousand Three Hundred Nine Paise SixtyFour Only
8	Construction of granular sub-base Grading V as Sub-Base and drainage layer by providing coarse graded crushed stone aggregates of granite/trap/basalt material, mixing in mechanical mix plant at OMC. Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98% proctor density, complete as per specifications. Clause 401 of MORTH V Revision. (Page No. 153. Item No.20.5)	Cum	92.16	1955.03	One Thousand Nine Hundred FiftyFive Paise Three Only

	SRRB M400-17: Providing, Laying, spreading and Compacting crushed stone aggregates of granite/ trap/ Basalt to wet mix macadam specifications including premixing the material with water at OMC in Mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406. (Page No. 155. Item No. 20.18)	Cum	122.88	1961.26	One Thousand Nine Hundred SixtyOne Paise TwentySix Only
10	KSRRB M500-6: Providing and Supplying primer coat with S.S bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg /sqm using mechanical means complete as per specifications Clause 502 of MORTH Clause 502 of MORTH V revision (P.No-158, Item No. 21.6)	Sqm	614.40	28.05	TwentyEight Paise Five Only
11	KSRRB M500-17: Providing and laying Dense Graded Bituminous Macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH table 500-10 complete in all respects complete as per specifications. MORTH Specification No,507. Using 100/120 TPH capacity HMP with sensor paver Gr-II (50mm to 75mm) with 4.5% VG-30 Bitumen (Page No. 160. I.No-21.17.6)	Cum	30.72	6465.49	Six Thousand Four Hundred SixtyFive Paise FourtyNine Only
12	KSRRB 500-7: Providing and applying tack coat using 80/100 grade bitumen (VG10) on the prepared black topped surfaces at 0.25kg per sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH Chapter 5 (Page No. 158. Item No. 21.7)	Cum	2618.60	12.47	Twelve Paise FourtySeven Only

Providing and laying bituminous concrete 50mm thick with hot mix plant, using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. Clause 507 of MORTH V revision as per IRC SP-53-2015. Do- using 40-60 TPH capacity HMP with mechanical paver grading II (30-45mm) with 5.4% of modified bituminous binder consisting of 4.97% of VG-30 Bitumen (60/70 grade) and 0.43% of plastomeric thermoplastics (waste plastic) (Page No. 171. Item NO.21.78.12)	Cum	78.56	7598.83	Seven Thousand Five Hundred NinetyEight Paise EightyThree Only
14 KSRRB M800-13: Road marking with Hot Applied 'Thermoplastic' Compound with Reflectorizing Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorizing glass beads at 250gms per sqm area, thickness of 2.5mm is exclusive of surface applied glass beads as per IRC:35.The Finished surface to be level , Uniform and free from streaks and holes complete as per Specifications. MORTH Specification NO.803 (P.No-182, I.No-24.15)	Sqm	102.40	445.65	Four Hundred FortyFive Paise SixtyFive Only

MS00-33. Shank Raised Pavement made of Polycarbonate and ABS (Acrylonitrile Butadiene Styrene) Moulded and reflective panels with micro lens capable of providing total reflection of the light entering the face and shall support a load of 16000 tested in accordance to Specifications Category A of MORTH Circular No RW/33023/10-97 - DO III D 11.06.1997. The height, width and length shall not exceed 50mm, 100mm and 102mm and with minimum reflective area of 13 Sqcm on each side and the slope to the base shall be 35 degree. The strength of detachment of the integrated cylindrical shanks, (of diameter not less than 19mm and height nor less than 30mm) from the body is to be a minimum value of 500 kg. Fixing will be by drilling holes on the road for the shanks to go inside, without nails and using epoxy resin-based adhesive as per manufacturer's recommendation and complete as directed by the engineer. (P. No-187, I. No-24.41)


Nos

126.00

350.08

Three Hundred Fifty Paise Eight Only


Signature of the Contractor


Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64
Bruhat Bengaluru Mahanagara Paliko
Yelahanka, Division